





कमला जल विद्युत परियोजना, गांव & डाकघरः बोआसिमला, थानाःरागा, जिला:कामले, अरुणाचल प्रदेश- ७९११२० Kamala H.E. Project, VIII. & PQ: Boasimla, PS: Raga, Distt.: Kamle, Arunachal Pradesh 791120 E-mail: khop@nhpc.nlc.ln

Ref. No.: NH/KHEP/WO/2025/410

Date: 11.02.2025

Work Order

To,

M/s J M ENTERPRISES, Poku, Lower Subansiri, Arunachal Pradesh, 791120

Subject: - Work Order for the work "Construction of crate wall/ gabion wall for retaining the muck generated from LDR 3 drift for Kamala HE Project."

Ref.: Your Consent letter No. Nil, dated 25.01.2025

Sir,

CC1/40Ch (

With reference to your letter dated 25.01.2025, on behalf of NHPC Limited, Kamala HE Project is pleased to issue work order for the "Construction of crate wall/ gabion wall for retaining the muck generated from LDR 3 drift for Kamala HE Project." for an amount of Rs. 4,53,655.00 (Rupees Four Lakhs Fifty-Three Thousand Six Hundred Fifty-Five only) as per the details annexed at Annexure-I with following terms and condition.

Terms and conditions: -

Prices: Rates shall be firm and inclusive of labour cost and material cost.

- 2. The work shall be executed as scope of work and specifications or as directed by the Engineer-in-Charge at site.
- 3. Deputy General Manager (Civil) shall be the Engineer-In-Charge and may be contacted immediately for execution of this work.
- 4. Paying Authority: SM (Fin.) Regional Office, Itanagar.
- 5. Payments Terms: 100% payment shall be made through online within 20 days after completion of work, inspection by authorized representative of NHPC Limited Kamala HE Project and submission of GST Invoice.
- 6. The completion period of the work is 1 month w.e.f 11.02.2025 to 10.03.2025. As time is the essence of the contract, no time extension shall be allowed excepting under force majeure clause.
- 7. Defect Liability Period for the work is 6 months after completion of work.

स्वहित एवं राष्ट्रहित में ऊर्जा बचाएं / Save Energy for Benefit of Self and Nation बिजली से संबंधित शिकायतों के लिए 1912 डायल करें / Dial 1912 for Complaints on Electricity CIN: L40101HR1975GOI032564


Power Behind Green Power

















(A Government of India Navratna Enterprise)



कमला जल विद्युत परियोजना, गांव & डाकचर: बोआसिमला, धाना:रागा, जिला:कामले, अरुणाचल प्रदेश- ७९११२० Kamala H.E. Project, Vill. & PO: Boasimla, PS: Raga, Distt.: Kamle, Arunachal Pradesh 791120 E-mall: khep@nhpc.nlc.ln

- 8. The security deposit @ 5% shall be deducted from the bill of the contractor. The amount of security deposit deducted from the contractor bill shall be released after Completion of defect liability period.
- 9. The Tax shall be deducted as per Govt. Rules.
- 10. Liquidated Damage: If the work is not completed within completion period, penalty @1/2% per week or part thereof (subject to maximum of 5%) of the order value shall be levied to the work. However, cost compensation for any time extension shall not be paid.
- 11. Transportation of men and material to site will be arranged/ borne by the contractor and nothing will be paid on this account.
- 12. The contractor shall comply all the relevant labour laws including EPF deduction in respect of contract employee under EPF & MP Act - 1952 and contract labour [Regulation and abolitions] Act - 70, including insurance.
- 13. All safety precautions shall be followed by the contractor during execution of the work. If any mishappening occurred due to negligence of labour, department shall not be responsible for the same.
- 14. Corporation reserved the rights to reject/cancel or amend the order without assigning any reasons whatsoever.

Yours Sincerel


Kamala HE Project

Copy to:

- HOP-Kamala HEP, for kind information please.
- DGM(Civil) for kind information and necessary action please.
- SM (Fin.) for kind information please. 3.
- Office file.

स्वहित एवं राष्ट्रहित में ऊर्जा बचाएं / Save Energy for Benefit of Self and Nation बिजली से संबंधित शिकायतों के लिए 1912 डायल करें / Dial 1912 for Complaints on Electricity CIN: L40101HR1975GOI032564

Power Behind Green Power

















कमला जल विद्युत परियोजना, गांव & डाकघर: बोआसिमला, थाना:रागा, जिला:कामले, अङ्णाचल प्रदेश- ७९११२० Kamala H.E. Project, VIII. & PO: Boasimia, PS: Raga, Distt.: Kamle, Arunachal Pradesh 791120 E-mail: khep@nhpc.nic.in

Annexure-I

SCHEDULE OF COST

Name of Work: Construction of crate wall/ gabion wall for retaining the muck generated from LDR 3 drift for Kamala HE Project.

Period: 1 Month

SI. NO.	Description	Unit	Quantity	Rate (RS.)	Amont (RS.)
1.	Providing and laying of boulder apron laid wire crates made with 4mm dia. GI wire confirming to IS: 280& IS: 4826 in 100mm X 100mm mesh (Weaved diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 40 kg each.	Cum	135	3,360.41	4,53,655.4
				Total	4,53,655.4
				Say	4,53,655.00

स्वहित एवं राष्ट्रहित में ऊर्जा बचाएं / Save Energy for Benefit of Self and Nation बिजली से संबंधित शिकायतों के लिए 1912 डायल करें / Dial 1912 for Complaints on Electricity CIN: L40101HR1975GOI032564

