

एन एच पी सी लिमिटेड NHPC LIMITED

(भारत सरकार का उद्धम) (A GOVT. OF INDIA ENTERPRISE)







तीस्ता-V पावर स्टेशन Teesta-V Power Station, Balutar

REQUEST FOR PROPOSAL (RFP)

Name of work: Request for technical and commercial proposal for "Protective Ceramic coating on Spiral Casing, Stay Vanes and Turbine Top Cover of Generating Units of Teesta-V Power Station".





REQUEST FOR PROPOSAL (RFP)

1. Online Request for technical and commercial proposal (RFP) from eligible **Sole Bidders** for the work of **"Protective Ceramic coating on Spiral Casing, Stay Vanes and Turbine Top Cover of Generating Units of Teesta-V Power Station."**

A. Brief details of the tender:								
SI. No.	Item	Description						
i)	Mode of tendering	e-Procurement System						
		Cover-I: Online Techno-Commercial Bid and price bid						
ii)	Tender ID No.	2024_NHPC_833160 _1						
iii)	Tender reference No.	NH/TSV/Cont/MC-148/NIT-965/2024-25/289 Dated: 30/10/2024						
iv)	Period of Bid Validity	120 days						
v)	Tender inviting	Dy. General Manager (Elect.)						
	Authority	Contract Division, Teesta-V Power Station, Balutar, Singtam Distt - Fast Sikkim-737134						
		E-mail: teestav-contract@nhpc.nic.in						
B. Critical dates of tender:								
vi)	Publishing Date & Time	30/10/2024 at 15:00 Hrs						
vii)	Document Download Start	30/10/2024 at 15:00 Hrs						
	Date & Time							
viii)	Pre bid meeting Date &	Not required.						
	Time							
ix)	Last date of Receipt of	02/11/2024 at 14:30 Hrs						
	clarification of Bid							
x)	Bid Submission Start Date	30/10/2024 at 15:00 Hrs						
	& Time							
xi)	Online Bid Submission	06/11/2024 at 17:30 Hrs						
	Closing Date & Time							
xii)	Online Bid Opening of	Venue: Contract Division, Teesta V Power Station,						
		Balutar						

Technical Bid and price bidDate: 09/11/2024 Time: 16:00 Hours(Cover-I)

- 2 Complete Bid Document /Tender Document can be viewed and down loaded from Central Public Procurement (CPP) Portal <u>https://eprocure.gov.in/eprocure/app</u>. The site can also be viewed through e-procurement corner of NHPC website www.nhpcindia.com and CPP Portal. Any Bidder who wishes to quote for this Tender can download the Tender Document from aforesaid portal after online Bidder registration for e-tendering.
- 3 **COURT OF COMPETENT JURISDICTION**: Any legal action taken or proceeding initiated on any of the terms of the contract shall be only in the jurisdiction of Hon'ble High Court of Sikkim.

4 Disclaimers

This RFP is neither an agreement and nor an offer by NHPC to the prospective Bidders or any other person. The purpose of this RFP is to provide interested parties with information that may be useful to them in submitting their proposals pursuant to this RFP includes statements, RFP. This which reflect various assumptions and assessments arrived in relation to the Project. This RFP document and any assumptions, assessments and statements made herein do not purport to contain all the information that each Bidder may require. The Bidder shall bear all its costs associated with or relating to the preparation and submission of proposal pursuant to this RFP. Where necessary, NHPC reserves the right to amend or supplement the information, assessment or assumptions contained in this RFP. NHPC also reserves the right to withdraw the RFP or foreclose the procurement case at any stage. The issuance of this RFP does not imply that NHPC is bound to shortlist a Bidder for the Project. NHPC also reserves the right to disqualify any Bidder should it be so necessary at any stage on grounds of National Security.

Requisite details in this regard are attached herewith as under for proposal:

- (i) Detail of Site Location.
- (ii) Scope of work.
- (iii) Drawings.
- (iv) Technical Specifications.
- (v) Tentative Special Conditions
- (vi) Technical & Commercial Offer

(i) detail of site location:

NHPC Ltd (A Govt. of India Navratna Enterprise), Teesta-V PS desires to construct a Prefab structure for Kendriya Vidyalaya at Teetsa-V Power Station, Balutar.



Teesta-V PS (510MW) is located in Gangtok District of Sikkim. The project envisages harnessing of Teesta water, between Dikchu and Sirwani. The site location (proposed prefab KV school) is in Left Bank side, Balutar. Proper approach road is available with adequate of space available for unloading of materials for the structure. Nearest Railway Station: - Siliguri, approximately 110 Kms from Teesta-V PS, Balutar. Nearest Airport: - Bagdogra, approximately 110 Kms from Teesta-V PS, Balutar. Nearest Bus Stop: - Singtam, approximately 06 Kms from Teesta-V PS, Balutar.

(ii) SCOPE OF WORK :

Name of Work: Protective Ceramic Coating on Spiral Casing, Stay Vanes and Turbine Top Cover of 3 nos Generating Units (Unit-1, 2,3) of Teesta-V Power Statione for HVAC system of Teesta V Power Station.

Scope of Work

1. Surface Preparation:

- Surface should be roughened by grit blasting/sand blasting, to achieve mechanical bonding. Surface roughness after grit blasting/sand blasting should be between 65-67 microns and same shall be ensured with profile gauge tester.
- After blasting, surface should be checked for defects, blow holes etc., the defects if any, to be rectified with appropriate action.
- Surface to be ceramic coated should be thoroughly cleaned and should be free from contamination, oil, grease and other foreign particles. Clean surface should be obtained by compressed air or application of an industrial cleaning solvent (solvent to be residue-free if used) based on the condition of substance.
- Area to be sprayed has to be kept confined at the time of sand blasting, so that all sprayed grit is collected in the filter media through the exhauster. The areas in the spiral which are not to be coated are to be properly masked from blasting and spraying.
- All necessary arrangements have to be ensured by the contractor for the blasting and surface preparation. Necessary in-situ assistance such as illumination, power supply and compressed air shall be provided by NHPC free of cost.
- Contractor shall arrange all the materials like ceramic coating, components epoxy filled with small ceramic bread, abrasion resistance material, wear resistance putty etc. which is required for protective ceramic coating.



The prepared surface shall be checked by Engineer-in-charge or his representative before the application of the materials.

2. Coating Requirements:

- Blending and application of the coating material shall be done by qualified/authorized engineer/applicator at site.
- Repair and rebuild the surface of spiral casing, stay vanes and top cover shall be carried out by applying Epoxy based wear resistance putty.
- For spiral casing: Application of 2 (two) coats of *Ceramic Base Epoxy brushable putty* to get a wet thickness of 400-500 microns.
- For stay Vanes: Application of one coat of *Ceramic Base Epoxy brushable putty* to get a wet film thickness of 250-275 microns. Once it becomes sticky, apply *Epoxy based wear resistance putty* (minimum thickness 6 mm) and then again apply brushable ceramic coating film thickness of 100-150 microns on it to make the surface smooth.
- For Turbine Top cover: Application of one coat of *Ceramic Base Epoxy brushable putty* to get a wet film thickness of 250-275 microns. Once it becomes sticky, apply *Epoxy based wear resistance putty* (minimum thickness 6 mm) and then again apply brushable ceramic coating film thickness of 100-150 microns on it to make the surface smooth.
- Allow curing of surface for 24 Hrs.
- > The Shore D Hardness of the used ceramic should be minimum 85.
- Oxygen mask, safety belts, safety helmets, exhaust fans etc shall be arranged by the contractor at his own cost as per the safety norms to ensure the safety of personnel. For applying putty at Turbine top cover, extra safety to be ensured for face and eye protection as the work to be performed at upward direction.
- The work shall be executed in winter season, when the temperature may be go down up to 4 to 7°
 C and the surrounding temperature inside the spiral casing may be less than the recommended

एन एच पी सी *र्रे म P C*

temperature of the material to be used. The contractor shall arrange necessary heating arrangement to achieve the desired temperature inside the spiral casing before starting of work.

- After completion of the work successfully as per the scope of work and satisfaction of Engineer-In-Charge or his representative, all empty containers shall be taken back by the contractor and site shall be cleared of the empty containers, packing materials, spilled paint/primer or any other unwanted materials which are not required after completion of work
- 3. Inspection and Testing:
 - The duly prepared surface prior and after sand/grit blasting and subsequent cleaning with suitable solvent shall be inspected by EIC or his representatives before application of bond coat.
 - The base coat/bond shall be checked for proper thickness i.e 400-500 microns (for spiral casing) and 250-275 microns (for stay vanes) by Elcometer/DFT/WFT gauge. The thickness of coating shall be checked randomly by EIC or his representatives. Duly calibrated instruments shall be provided by the firm along with calibration certificate.
 - The final coat with ceramic beads filled coating of 06 mm thickness (for stay vanes & top cover) shall be checked by Elcometer / DFT/WFT gauge. The thickness of coating shall be checked randomly by EIC or his representatives. Duly calibrated instruments shall be provided by the firm along with calibration certificate.

The hardness of ceramic coating shall be checked randomly by EIC or his representatives by hardness meter/instrument. Duly calibrated instrument shall be provided by the firm along with calibration certificate.



(iii)Drawings.:









(iv) TECHNICAL SPECIFICATIONS:

Consumable Materials for providing for surface protective coating on Spiral Casing, stay vanes and turbine top cover.

Sl	Material	Material specifications				
No.	Description					
1	Ceramic Based Epoxy Brushable Putty	 Compressive strength equal or more than 10000 psi Conforming ASTM D695 or its equivalent standard. Hardness equal or more than 85 Shore D Conforming to ASTM D2240 or 				
		its equivalent standard.				
		3. Tensile Strength equal or more than 4000 psi conforming to ASTM D638 / its equivalent standard OR Adhesive Tensile Strength equal or more than 2000 psi conforming to ASTM D1002 or its equivalent standard.				
		4. Flexural strength equal or more than 8000 psi conforming to ASTM D790 or its equivalent standard.				
2	Epoxy Base Wear Resistant coating	1. Compressive strength equal or more than 11000 psi conforming to ISO 604 or its equivalent standard.				
		2. Hardness more than 80 Shore D conforming to ASTM D2240 or its equivalent standard.				
		3. Tensile Strength more than 2500 psi conforming to ISO 527-2 or its equivalent standard.				
		4. Flexural strength more than 7000 psi conforming to ASTM D790 or its equivalent standard.				

(v) The bidder shall submit the test certificates of the materials from manufacturer before carrying out the work as per scope of work.

$(v) \quad {\tt TECHNICAL \ SPECIFICATIONs:}$

1. Brief Details of Work: Work will be executed during upcoming annual maintenance of the units (tentatively in lean season i.e., Oct'24 to Jan'25) as per schedule intimated by Engineer-In-Charge separately. 45 days prior intimation regarding commencement of work will be notified by Engineer-In-Charge for mobilization of man power, equipments & materials to carry out the *"Protective Ceramic coating on Spiral Casing, Stay Vanes and Turbine Top Cover"*. In case contractor do not mobilize their man power well in advance or sufficient man power/ material are not arranged by the contractor which may likely affects the schedule of annual maintenance or to delay in completion of annual maintenance, in such a situation NHPC will foreclose the contract for the particular unit. On the event of non execution of the contract due to the reasons attributable to

the contractor, no claim of any nature shall be entertained by the Corporation and compensation if any to be levied shall be dealt as per provision of contract.

- **2.** Contractor will supply all the requisite materials related to the work of protective ceramic coating well in advance at least 30 days before commencement of work.
- **3.** Inspection: NHPC representative shall carry out stage inspection as per following manner:
 - (i) Material Inspection: The supplied materials for commencement of work shall be inspected by E-I-C or his authorized representative on receipt of the same at site. At the time of Inspection of the material product expiry date of the materials should be at least one year.
 - (ii) After carry out grit blasting / sand blasting the roughness of the surface shall be checked by E-I-C or his authorized representative as per scope of work.
 - (iii) Inspection after application of coating: The thickness of coating in spiral casing to be achieved in the range of 400 to 500 micron. The thickness of coating at stay vane to be maintained in the range of 250 to 270 micron after first coating and all the applicable process should be carried out as per sequence of scope of work, thereafter for preparation of smooth surface, application of 100 to 150 micron brushable putty to be ensured by the inspector. Similar inspection procedure shall be adopted to carry out stage inspection of Top cover as well.
- 4.0 Completion Period: The total completion period is 30 (Thirty) days for all the three units for the works under the scope of the contractor. One unit will be taken for "Protective Ceramic coating on Spiral Casing, Stay Vanes and Top Cover of the Generating Unit " at a time and there may be a suitable gap of minimum 3 days in between the commencement of work for the next two units. The actual completion date for each unit shall be taken from the actual date of handing over the unit to the contractor to the actual date of handover of the unit back to the NHPC after completion of the work of each unit. The overall completion of the work shall be computed by adding the number of days taken against each unit. The work will be carried out around the clock, preferably in three shifts. For mobilization of manpower, a mobilization period of 45 days shall be allowed to the contractor from the date of intimation for the commencement of the work.
- 5.0 **DEFECTS LIABILITY PERIOD**: The "Defect Liability Period" for the entire work under the Contract will be for 03 seasons (01 season means date of completion of annual maintenance in which work is completed, to the date of start of annual maintenance of subsequent financial year). If during the Defects Liability Period complete erosion (means original surface appears) exceeds 10% of the total coating area, same shall be repaired/rectified/replaced during annual maintenance of subsequent financial year. In case contractor does not complete the work in the allocated time slot available during annual maintenance of that particular generating unit, then

the PBG/SD of the contractor shall be forfeited. Generally generating units are not run beyond the silt content of 3000 PPM during non-lean season but for a short duration silt content can go up to 8000 PPM not exceeding 24 Hours aggregately during one entire season.

- 6.0 Arrangement for accommodation of supervisor and working personnel will be provided by NHPC on paid basis if available, otherwise, the contractor shall arrange their accommodation. No local transport facility shall be provided by NHPC.
- 7.0 Complete Insurance of all the work force and material shall be the total responsibility of the contractor. NHPC will not be liable for any such expenditure. The firm should comply all related labor laws and other statutory regulations required to carry out the work. All liabilities to the workmen will be borne by the firm. Firm should give declaration certificate before final payment that all the statutory laws are complied with by the firm and in case any short fall is found, what so ever, in respect of statutory requirement (such as labor payment, EPF etc.) at any point of time on later stage, the firm will be sole responsible to resolve the issues at our own cost and time for said work.
- 8.0 The Contractor shall not deploy any person below the age of 18 years.
- 9.0 The bidder shall submit the test certificates of the materials from manufacturer before carrying out the work as per scope of work.

10.0 Payment terms:-

Payment shall be made in the form of RA bill on completion of the job of each unit, fulfilling other conditions of LOA and on submission of bill along with requisite documents required to process the bill.

11.0 Liquidity Damages (LD): The contractor has to take all efforts to complete the work in stipulated time as per the contract subject to satisfaction of the EIC. If the contractor fails to complete the work within the scheduled completion period as specified, the contractor shall be liable to pay LD@0.035% of the contract sum of per day or part thereof for the period of delay subject to maximum of 10% of the value of the contract sum.

12.0 <u>CONSIGNEE:</u>

Engineer-in-Charge



(vi) Technical & Commercial Offer:

Name of Work: Protective Ceramic coating on Spiral Casing, Stay Vanes and Turbine Top Cover of Generating Unit # 3 of Teesta-V Power Station.										
SI. No.	Description	Unit	Qty. (Sq. Meter)	Rate (Rs.)	GST @ %	Rate (₹) with % GST	Final Rate (₹)	Amount (₹)		
1	Supply & Application of Brushable Ceramic Coating on Spiral Casing as per the scope of work and technical specification.	Sq. Meter	725.67							
2	Supply & Application of Ceramic Breads filled coating on Stay Vanes and top cover as per the scope of work and technical specification.	Sq. Meter	123.63							
	Grand Total (Rs.)									
In words:										

Notes:- 1) SAC Code of BOQ Items of Contract:

2) Offered Rates (on RFP) should be inclusive of all taxes including applicable GST, transportation charge, local octroi & all other charges and should be quoted in manually on the above table.

(For & on behalf of NHPC Ltd.)

Dy. General Manager (Elect.) Contract Division Teesta-V Power Station Email: teestav-contract@nhpc.nic.in

(Seal & Signature of Participated Firm)



BRIEF DESCRIPTION OF THE PROJECT

1. 1.1 ABOUT SIKKIM AND TEESTA RIVER.

- Sikkim is a small and beautiful state located in the northeast Himalayas. It is one the youngest state of Indian union. It is surrounded by vast stretches of Tibetan plateau in the north, Chubi valley of Tibet and Kingdom of Bhutan in the east, Darjeeling Gorkha Hill council in the south and kingdom of Nepal in the west.
- Due to prevalent cold and moderate climatic conditions with very low ambient dual level, the state presents ideal opportunity for development of high-tech industries like microelectronics and ancillary products which impose less burden on transportation facilities and earn rich dividends. However, for such developmental efforts, abundance of cheap and clean power is vital.
- Sikkim is drained by a large number of perennial rivers, the prominent ones being Teesta and Ragit. The Teesta river originates from Zemu glacier and Rangit river from Talung glacier in west Sikkim which, after flowing for about 60kms, joins the Teesta river near the state border with West Bengal.
- The elevation of Sikkim ranges from 300 m to 8583 m above mean sea level. It consists of lower, middle & higher hills.

1.2 LOCATION OF THE PROJECT

Nearest Railway Station :- Siliguri, approximately 110 Kms from Teesta-V PS, Balutar.

Nearest Airport :- Bagdogra, approximately 110 Kms from Teesta-V PS, Balutar.

Nearest Bus Stop :- Singtam, approximately 06 Kms from Teesta-V PS, Balutar.

1.3 BRIEF DESCRIPTION OF THE PROJECT

Teesta HE project, stage-V is located in South-East Sikkim. The project envisages harnessing of Teesta water, between Dikchu (27º 24' 00" E: 88º 31'30"N) and Sirwani (27º14'54"E: 88 29' 56"N). The scheme comprise; 95m high Concrete Gravity Dam (located 2 Kms downstream of its confluence with Dikchu nala) 17.106 Km long HRT housed on the left bank, a 95m high, 30m dia Surge Shaft and an underground power house near Sirwani, to generate 510MW of Power, utilizing a gross head of 200m.